

Fire Ribbon Direct Vent Vu Thru 6 ft

MODEL NO.

612 with mandatory safety screens

Viewing Area
Exterior Dimension
Framing Dimension
Gas Type*
Gas Connection
On/Off
Efficiency
Venting Options

73.25" W x 12.75" H
87.625" W x 30.25" H x 12" D
89.75" W x 31.5" H x 12" D
Natural, LP/Propane conversion kit included
3/8"
Programmable/thermostatic remote control
Up to 72.6/76.9%
Through exterior wall or vertical through roof.
2ft vertical rise required within a horizontal termination run. Must keep within a 10' max. horizontal run.

Vent Type

DuraVent DirectVent Pro 46DVA. Unit supplied with starter collar & wall pass through
2 Variable speed fans
1 110V with battery back-up
27,000 - 34,000 BTU/h
28,000 - 40,000 BTU/h
2 Fixed ceramic glass panel
Reflective black porcelain enamel firebox liner

Fan
Electric
BTU input Natural gas
BTU input LP/propane
Doors/glass
Interior Color
Sustained operating gas pressure parameters:

5.5" - 10.0" w.c. for natural gas
11.0" - 13.0" w.c. for LP/Propane
Omni-Test Laboratories Report #0361GF006S
Icerglass or Ebonyglass
1/2 inch Satin black trim
1/2 inch Stainless steel trim
Wall switch kit
Power vent for long runs

Certifications
Included
Options
*Must be specified at time of ordering.

Note: This is a high throughput gas appliance and critical attention is needed to size the gas pipes properly.

